

ADDENDUM No. 1

Date: June 12, 2026 **Project No:** M25007
Project Name: Request for Proposal: Town of Shelburne, Main Street Resurfacing
To: All Bidders

This Addendum consists of 3 pages total.

Please make the following changes / additions to the Request for Proposal Document. Bidders are responsible to ensure that all addenda have been received. Bidders are required to acknowledge addenda in the space provided in Section B of the Form of Proposal.

This addendum will form part of the terms, conditions and specifications outlined in the above noted Request for Proposal Contract Document. All other components of the Bid documents shall remain unchanged.

GENERAL INSTRUCTIONS

1. The following Contractors were in attendance for the non-mandatory site visit held on Tuesday, June 9, 2026, at 9:00 a.m. Eastern Time at the back parking lot of the Town of Shelburne municipal offices located at 203 Main Street East, Shelburne, Ontario:
 - Cox Construction Limited.
 - GIP Paving Inc.
 - Ashland Construction Group Ltd.
2. Bidders shall REMOVE & REPLACE page 20 of the Schedule of Unit Prices (1 page) concerning quantity and unit item revisions as follows:
 - Adjust Item B4 - revise unit to tonnes and quantity to 312.
 - Adjust Item B5 - revise unit tonnes and quantity to 240.
 - Adjust Item B6 - revise unit tonnes and quantity to 90.

QUESTIONS AND RESPONSES

Question 1: Will the Town permit night work?

Response 1: Yes, however, east-west traffic along Main Street is to remain open along with the full intersection at Owen sound Street. Victoria Street and William Street may be closed.

Question 2: Can sub-excavation items be measured per ton.

Response 2: Yes, refer to General Instruction No. 2.

Question 3: Can the line painting item be broken down by type per linear metre?

Response 3: Line painting price shall be provided in lump sum. Scope of line painting shall be all required paint to replace existing lines disturbed during resurfacing work. This includes centre lines, parking stalls, stop bars, pedestrian crossings and intersection diagonal lines at Main Street and William Street. Any line painting requested by the Owner at time of construction, not shown on the Contract Drawing will be paid out as additional work, however, this is not expected.

I have read the foregoing Addendum and have considered it in my Proposal.

_____ Bidder's Name
_____ Signature
_____ Date

M25007_Add#1_FINAL_2026-06-12.docx

SCHEDULE OF UNIT PRICES

Schedule B: Main Street Resurfacing (William Street to Owen Sound Street)					
ITEM	DESCRIPTION OF WORKS	ESTIMATED QUANTITY	UNIT	UNIT PRICE	TOTAL PRICE
B1	Milling – Roadway, Full Depth	1810	m ²	\$	\$
B2	Milling – Lap Joints, 2m Width	50	m	\$	\$
B3	Temporary Ramping and Removal	1	LS	\$	\$
B4	*(PROVISIONAL) Sub-Excavate and Dispose of Unsuitable Granular Base Materials	312	Tonnes	\$	\$
B5	*(PROVISIONAL) Supply, Place and Compact Granular 'B'	240	Tonnes	\$	\$
B6	*(PROVISIONAL) Supply, Place and Compact Granular 'A'	90	Tonnes	\$	\$
B7	Fine Grading of Granular Base, Including Crowning with Minimum 2% Crossfall from Centreline of Road	1810	m ²	\$	\$
B8	Hot Mix Asphalt – Superpave 19.0 at 50mm, Including Intersection Quantities	1810	m ²	\$	\$
B9	Hot Mix Asphalt – Superpave 19.0 at 50mm, Including Intersection Quantities and Tack Coat	1810	m ²	\$	\$
B10	Hot Mix Asphalt – Superpave 12.5 FC2 at 40mm, Including Intersection Quantities, Lap Joint and Tack Coat	1910	m ²	\$	\$
B11	Road Painting to Match Existing	1.0	LS	\$	\$
SUB TOTAL					\$

* The requirement for Provisional items is dependent on the results of geotechnical inspections following asphalt milling. Such items shall only be performed with prior written authorization from the Owner and Engineer. Payment for these items will be made only when authorization is granted before work begins.